

CHECKBOX 16 PLUS

SEAWARD
Tried. Tested. Trusted.

Installation instrument Check Point.

The CheckBox 16 Plus is a convenient Installation Instrument Check Point. It is a versatile compact instrument which is designed to provide a convenient check point for installation test instruments including Earth Loop Testers, Insulation Continuity Testers and RCCB Testers. The CheckBox 16 Plus provides a convenient and simple method of confirming the functionality and accuracy of Installation Tester readings as required for NICEIC inspections.

The CheckBox 16 Plus checks all Seaward and most other manufacturer's installation test instruments.

NICEIC & IET compliant

16th/17th Edition testing

Continuity and insulation check

Proving voltage

Loop and RCD test

Compact

SPECIFICATIONS

Tests Performed

Continuity check against precision 1ohm and 10ohm
Insulation check against precision 1Mohm
Earth Loop Impedance/Resistance check against 5ohm
RCD 60mS Trip Time and 30mA test current check
Voltage measurement check 45 — 85v a.c. specific value for each unit

ADDITIONAL INFORMATION

Power Mains 230V 50Hz
Weight & Dimensions 0.44kg / 18cm x 4.4cm x 9.6cm

Checkbox 16 part number: 295A914

